BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division,

Tender No: BBMP/EE/DD/TEN/01/12-13 Date: 17.05.2012 Item No: 11

SCHDULE-B

NAME OF WORK: Ward Maintainance of Desilting of Drains, Tractor & JCB in ward no: 13 in Shettyhalli Sub-Division

Sl. No	Description of work	Unit	Quantity	Rates Quoted by Contractor	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Supply of the 4**OHP** Tractor on daily rate basis to the required place as per the direction of the Engineer in charge	Per Day	360.00	1356.00	Rupees One Thousand Three Hundred Fifty Six Only
2	Supply of the **Labour** Heavy Mazdoor to the required place as per the direction of the engineer in charge	Per Day	3600.00	192.00	Rupees One Hundred Ninety Two Only
3	JCB Excavator	Per Day	10.00	7029.00	Rupees Seven Thousand Twenty Nine Only
4	Tipper	Per Day	10.00	2008.00	Rupees Two Thousand Eight Only
5	Removing & Resetting of Footpath Slabs	Sqm	834.00	100.00	Rupees One Hundred Only
6	Removing & Resetting of Curbs	m	682.00	50.00	Rupees Fifty Only
7	KSRB 5.3-3 Providing and constructing granite / trap / basalt rubble stone masonry in foundation with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.	Cum	24.00	3333.00	Rupees Three Thousand Three Hundred Thirty Three Only

Signature of the Contractor

Executive Engineer 17/8

8	KSRB 4.2.2 : Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 340kgs, with with 20mm and down size graded granite metal, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, return walls, walls (any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM of machinery, curing, complete as per specifications.	Cum	31.32	5182.00	Rupees Five Thousand One Hundred Eighty Two Only
9	Removing B.S.Slab of drain and stacking etc., complete	Cum	436.05	49.00	Rupees Forty Nine Only
10	KSRB 4.9.2: providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications.	Qtls	11.00	6553.00	Rupees Six Thousand Five Hundred Fifty Three Only
11	Refixing stone slabs of drains and pointing in CM 1:3 etc complete	Sqm	436.05	61.00	Rupees Sixty One Only
12	Providing & laying reinforeced cement precast slabs of mix CC 1:11/2:3 using 20mm & down size graded Granite metal using HYSD 10mm dia steel @ 100mm c/c both ways & Complete as per specfications.	Sqm	27.00	2054.00	Rupees Two Thousand Fifty Four Only
13	Providing Granite slabs selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete 7.5 cms thick	Cum	76.95	336.00	Rupees Three Hundred Thirty Six Only

Signature of the contractor

Executive Engineer
Dasarahalli Division
B.B.M.P